PRODUCTION SCHEDULE

The workroom collection.

The garden house · Alex & Morgan Taylor (fictional clients)
APX-SAMPLE · 2 windows

Apex allowance: every cut width uses the window's longest finished drop, as a full rectangle. No triangular offcuts are deducted. Quantities include the recorded extra allowance; suitable offcuts may be used for tiebacks after checking grain, pattern and size.

ROOM AND WINDOW	FACE FABRIC	LINING
Drawing room · Garden apex	23.16 m	23.16 m
Principal bedroom · Main window	11.44 m	11.44 m

Material order summary

Fabric · Illustrative collection SAMPLE-01 / 1400 mm roll · Warm flax	23.16 m
Lining · SAMPLE-BLACKOUT / 1400 mm roll · Ivory	34.60 m
Fabric · Illustrative collection SAMPLE-01 / 1400 mm roll · Soft sage	11.44 m

Confirm supplier order increments, required batch and availability before ordering. Full-width panel allocation is conservative; any alternative layout must be reviewed by the workroom.

Standard curtain care

Professional dry cleaning only. Do not machine wash, hand wash, soak, bleach or tumble dry. Ask a curtain-cleaning specialist to check the sewn-in care labels, face fabric, lining, interlining and trims before treatment. If a label conflicts with this guide, contact Apex before cleaning.

APEX CURTAINS

WORKROOM / GARDEN APEX

Drawing room

Alex & Morgan Taylor (fictional clients) · APX-SAMPLE · All cutting dimensions in millimetres

FACE FABRIC / ORDER

23.16 m

6 widths × 3860 mm

Roll width: 1400 mm
Finished drop: 3600 mm
Top + bottom allowance: 260 mm
Extra ordered: 0 m

LINING / ORDER

23.16 m

6 widths × 3860 mm

Roll width: 1400 mm
Finished drop: 3600 mm
Top + bottom allowance: 260 mm
Extra ordered: 0 m

Lining order matches face fabric. Lining cutting requirement: 23.16 m. Use the longest drop across the full rectangle. Do not deduct apex offcuts. Pattern cuts include the recorded matching allowance.

01 / Window measurements

Two-sided apex; width 3200 mm; left 2400 mm; middle 3600 mm; right 2400 mm; longest 3600 mm.

Left slant 2000 mm; right slant 2000 mm; peak 1600 mm from left. Calculated from the entered dimensions, rounded to the nearest mm.

02 / Making & finishing

Fabric	Illustrative collection · Textured linen · SAMPLE-01 · Warm flax
Heading & panels	Double pinch pleat · 2× fullness · 2 panel(s) · Centre opening
Pattern	plain; vertical repeat 0 mm; horizontal 0 mm; motif allowance 0 mm
Width allowances	Side hems 40 mm; seams 15 mm; returns 0 mm; overlap 0 mm
Length & lining	Touching the floor · blackout · SAMPLE-BLACKOUT · Ivory
Tiebacks	2 × Matching fabric · Warm flax
Hooks / holdbacks	2 × Classic holdback · Bronze
Track	Forest Group CS® Contract System · White

Drawing room · notes & photographs

Soft, generous folds echo the height of the glazing, with warm natural tones that sit quietly beside the garden.

APEX CURTAINS

WORKROOM / MAIN WINDOW

Principal bedroom

Alex & Morgan Taylor (fictional clients) · APX-SAMPLE · All cutting dimensions in millimetres

FACE FABRIC / ORDER

11.44 m

4 widths × 2860 mm

Roll width: 1400 mm
Finished drop: 2600 mm
Top + bottom allowance: 260 mm
Extra ordered: 0 m

LINING / ORDER

11.44 m

4 widths × 2860 mm

Roll width: 1400 mm
Finished drop: 2600 mm
Top + bottom allowance: 260 mm
Extra ordered: 0 m

Lining order matches face fabric. Lining cutting requirement: 11.44 m. Use the longest drop across the full rectangle. Do not deduct apex offcuts. Pattern cuts include the recorded matching allowance.

01 / Window measurements

2200 mm width; 2600 mm finished drop.

Horizontal track.

02 / Making & finishing

Fabric	Illustrative collection · Textured linen · SAMPLE-01 · Soft sage
Heading & panels	Double pinch pleat · 2× fullness · 2 panel(s) · Centre opening
Pattern	plain; vertical repeat 0 mm; horizontal 0 mm; motif allowance 0 mm
Width allowances	Side hems 40 mm; seams 15 mm; returns 0 mm; overlap 0 mm
Length & lining	Touching the floor · blackout · SAMPLE-BLACKOUT · Ivory
Tiebacks	2 × Matching fabric · Soft sage
Hooks / holdbacks	2 × Classic holdback · Bronze
Track	Forest Group KS® Klick System · White

WORKROOM REFERENCE / MAIN WINDOW

Principal bedroom · notes & photographs

Gentle sage and beautifully structured folds bring a restful rhythm to the bedroom. Ivory blackout lining completes the specification, with matching tiebacks and bronze details.